## A MEMBER OF







## **OILFIELD EQUIPMENT & VESSELS MANUFACTURERS L.L.C**

... Engineers With Excellence

www.sptllc-ress.com

Al Ghail Industrial Park | Ras Al Khaimah | UAE | P.O Box 14638

+971 7 258 9131 Info@sptllc-ress.com





GPS: 25.390833, 55.984722



# PRESENTATION

FLATPACK MODULAR HOUSING.




### Classic-type

The milestone of the modular accommodation industry: flat-packed, modular, versatile, stackable.

**Flexible living space for temporary or permanent use**. Flatpack modules have 20' dimensions (external dimensions: 6.055 x 2.435 x 2.79h mt.


They are joinable without limit to create bigger areas. Stackable in buildings of up to 3 floors.




### Essential-type

The **cost-effective version of the Multi House module**: great value for money. Even though built with cost effective materials it is engineered like our classic "multi house" flat pack.

It maintains all features of the flat pack: fully modular, joinable, stackable and shipped in bundles. That is the "essence" of Multi House.



#### INTRODUCTION: MODULAR FLAT PACK UNIT



The **Modular FLAT PACK unit** or container is designed as a light, solid construction Multi House system consisting of STEEL floor and roof frames and corner profiles.

The system enables compounding of individual containers in longitudinal and transverse directions without limits. It also enables compounding of containers in 2 floors in height (ground floor + first floor), or in 3 floors in height for warehousing of these containers (ground floor + 2 floor).

Wainscots of the container are made of light insulation panels and offer pleasant climate in the interior due to their building and physical properties.




#### 20' Flatpack container arrangements

Flat pack containers can be joined to form much larger structures and compounds fit for long-term storage and housing purposes. The modularity of each individual container makes it possible to develop large structural designs of considerable complexity relatively easily.

Flatpack modules have 20' dimensions (external dimensions:  $6.055 \times 2.435 \times 2.79h$  m); they are joinable without limit to create bigger areas. Stackable in buildings of up to 3 floors

Ground floor level -can be joined/linked horizontally on both long and short sides



Being a modular container, it can be joined to create larger spaces and can be stacked 3-high.

Offered layouts for a standard 20foot unit range from single or double room to ablution and sanitary containers.

Multi House is the flat-pack container renowned all over the world.


Individual units or composite and modular structures for all accommodation Solutions in hot and cold climates.

Ideal solution whenever you have a need for any "off the shelf" containerized space.

# **MODULAR** [living units] with TERRACE


- AREA = 60 Sq Mtrs.
- ARCHITECTURAL drawings
- 2D FLOOR [plan] and 3D FLOOR [plan]
- 2D BUILDING [elevations] and 3D BUILDING [elevations]
- 3D BUILIDNG [sections]
- BLOW up 3Ds
- 3D [impressions]










FLOOR [plan]









2D BUILDING [elevations]



view at [D]



view at [B]



view at [D]




view at [B]






3D BUILDING [sections]



BLOW [up] 3D [view]



BLOW [up] 3D [view]



MODULAR 20' FLAT PACK CONTAINER UNITS



MODULAR 20' FLAT PACK CONTAINER UNITS




MODULAR 20' FLAT PACK CONTAINER UNITS

# MODULAR [living units] with TERRACE


- AREA = 45 Sq Mtrs .
- ARCHITECTURAL drawings
- 2D FLOOR [plan] and 3D FLOOR [plan]
- 2D BUILDING [elevations] and 3D BUILDING [elevations]
- 3D BUILIDNG [sections]
- BLOW up 3Ds
- 3D [impressions]










FLOOR [plan]







view at [B]





view at [D]





view at [D]




view at [B]





# 3D BUILDING [sections]

PROPOSED MODULAR LIVING UNITS with TERRACE







BLOW [up] 3D [view]

# **MODULAR** [living units] with TERRACE

- AREA = 30 Sq Mtrs.
- ARCHITECTURAL drawings
- 2D FLOOR [plan] and 3D FLOOR [plan]
- 2D BUILDING [elevations] and 3D BUILDING [elevations]
- 3D BUILIDNG [sections]
- BLOW up 3Ds
- 3D [impressions]







# FLOOR [plan]

MODULAR 20' FLAT PACK CONTAINER UNITS


#### **Modular Flatpack container dimensions:**


Length: 6.055 meters


Width: 2.435 meters


External height: 2.790 meters

Internal height: 2.50 meters









view at [B]

view at [C]



view at [D]



view at [B]



3D BUILDING [sections]

# Mod 104 vip Single room with en-suite bathroom Mod 114a 2 rooms with shared central bathroom






# Mod 104 Double room Mod ablution

Equipped according to customer's need with a mix of sanitary components





# Assembly Procedure

Pre-Fabricated

Modular Container Living


## Tools Needed.





key








#### WARNING:

Do not handle the bundle with forklift truck or side Stacker






#### Do not lift more than 1 kit at a time




#### Position the kit in the assembly area




## Remove the caps sealing the hole of the roof drain pipes




## Remove the screws locking the bundling columns




#### Lift the roof through the holes of the corner castings




## The kit contains all necessary components for a proper assembly



## Remove all the components from the base




#### Position the corner posts




Fix the corner post by using M12 x 40 screws. Keep it loose to allow adjustment when installing the roof






#### Position the roof frame




## Once the roof frame is set, tighten the nut of the threaded pins



## Tighten all screws on all 4 corner posts




Seal the bottom joints between the floor frame and corner posts with silicon




Seal the top joints between the roof frame and corner posts with silicon







#### Approved layout




# Insert the locking plates on the panel top threaded rods




## Tighten the locking plates with M8 bolt and washer







#### Insert the threaded iron rod locking plate




## Tighten it with M10 bolt and washer







In short side, position the panel 40 mm from the corner post




#### Drill a 5cm hole in the corner post reinforcements



#### Fix the end panels with 90mm long screws



## Location of corner post reinforcements




Wall panels are interchangeable, however, this will affect the position of sockets and switches and length of electric cables



Fit the PVC drain pipes on 4 corners – Insert the bottom part, then bend it a little and push top end to upper corner




Wiring system for units with Sandwich mineral wool panels Cables installed in between panels




Wiring system for units with Sandwich mineral wool panels Cables installed in between panels



### Wiring system for units with Chipboard panels Insert pre-wired conduits into junction box




Wiring system for units with Chipboard panels
Plug cables in the connector




Wiring system for units with

Chipboard panels


Connect all poles (match cable colors)



#### Install lighting fixtures on ceiling



#### Pull the cables through the panel pre-drilled holes





#### Install the cables to the socket/switch and the cover plate





















# Folding Type Housing.



#### Easy installation: 4 workers + 10 mins=1 house







































## Open Event Ground Built Using Flat Packs.
























Packing /Loading / Logistics Handling .

## 20' Flatpack container Types of packing







# 20' Flatpack container Types of packing

20' bundles (**3 to 4 complete units**and up to **6 units of frames and columns only** per bundle)

Trans pack –loose components of **6 complete units**packed inside 40' high cube iso shipping container









## 20' Flatpack container Types of packing











Project Views.






Second floor level can be joined/linked vertically on G+2 level maximum Second floor level -can be joined/linked vertically on G+2 level maximum



## Interrior Views









### 20' FLATPACK CONTAINER ACCESSORIES



Step 1: Before installing the container house, make sure the foundation is flat
It's better to have cement foundation.



#### A MEMBER OF








### **SPT**



... Engineers With Excellence





Al Ghail Industrial Park | Ras Al Khaimah | UAE | P.O Box 14638 +971 7 258 9131 | Info@sptllc-ress.com



GPS: 25.390833, 55.984722

